



### INFRARED HEATING REQUIREMENTS

1. (4) LTU130-40 VENTED SPACE-RAY/INFRARED HEATERS. INSTALL AT 22 FT. ABOVE FINISHED FLOOR.
2. (2) SPACE-RAY SETBACK 5000 THERMOSTATS MOUNTED 56" ABOVE FINISHED FLOOR.
3. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
4. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
5. CONSULT HEATER SPECIFICATION SHEET AND "I & O" INSTRUCTIONS FOR FURTHER INFORMATION PLEASE VISIT [WWW.SPACERAY.COM](http://WWW.SPACERAY.COM).



Title: AIRCRAFT HANGAR  
INSTALLATION DETAIL-970

Drawn By: R.J. Harrington Date: 07 MAR 06