



INFRARED HEATING REQUIREMENTS

1. (4) ETS150-40 VENTED SPACE-RAY INFRARED HEATERS. INSTALL AT 25 FT. ABOVE FINISHED FLOOR.
2. (2) SPACE-RAY SETBACK 5000 THERMOSTATS MOUNTED 5'6" ABOVE FINISHED FLOOR.
3. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
4. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
5. CONSULT HEATER SPECIFICATION SHEET AND "I & O" INSTRUCTIONS FOR FURTHER INFORMATION PLEASE VISIT WWW.SPACERAY.COM

SPACE-RAY
INFRARED GAS HEATERS

Title: AIRCRAFT HANGAR
INSTALLATION DETAIL-971

Drawn By: R.J. Herrington Date: 07 MAR 06