



**INFRARED HEATING REQUIREMENTS**

1. (5) LTS130-30 VENTED SPACE-RAY INFRARED HEATERS. INSTALL AT 18 FT. ABOVE FINISHED FLOOR. (HEATERS 1 TO 5)
2. (2) LTU80-30 VENTED SPACE-RAY INFRARED HEATERS. INSTALL AT 18 FT. ABOVE FINISHED FLOOR. (HEATERS 6 & 7)
3. (1) LTU75-30 VENTED SPACE-RAY INFRARED HEATER. INSTALL AT 18 FT. ABOVE FINISHED FLOOR. (HEATER 8)
4. (2) LTU130-40 VENTED SPACE-RAY INFRARED HEATERS. INSTALL AT 18 FT. ABOVE FINISHED FLOOR. (HEATERS 9 & 10)
5. (1) CBS0 VENTED SPACE-RAY INFRARED HEATER. INSTALL AT 18 FT. ABOVE FINISHED FLOOR. (HEATER 11)
6. (6) SPACE-RAY RT SERIES THERMOSTATS MOUNTED 56" ABOVE FINISHED FLOOR.
7. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
8. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
9. CONSULT HEATER SPECIFICATION SHEET AND I & O INSTRUCTIONS. FOR FURTHER INFORMATION PLEASE VISIT [WWW.SPACE-RAY.COM](http://WWW.SPACE-RAY.COM)



Title: **AUTO DEALERSHIP  
INSTALLATION DETAIL-966**

Drawn By: **RJ Harrington**

Date: **07 MAR 06**