



INFRARED HEATING REQUIREMENTS

1. (8) LTU75-30 VENTED SPACE-RAY INFRARED HEATERS. INSTALL AT 15 FEET AND AT A 30° ANGLE ABOVE FINISHED FLOOR.
2. (4) SPACE-RAY RT SERIES THERMOSTATS MOUNTED 56" ABOVE FINISHED FLOOR.
3. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
4. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
5. CONSULT HEATER SPECIFICATION SHEET AND I & O INSTRUCTIONS. FOR FURTHER INFORMATION PLEASE VISIT WWW.SPACERAY.COM



Title: ICE HOCKEY ARENA
INSTALLATION DETAIL-961

Drawn By: R.J. Harrington Date: 16 JUN 05