



INFRARED HEATING REQUIREMENTS

1. (6) LTU100-30 VENTED SPACE-RAY INFRARED HEATERS, INSTALL AT 15 FT. AND AT A 30° ANGLE ABOVE FINISHED FLOOR.
2. (2) SPACE-RAY SET-BAK 5000 THERMOSTATS MOUNTED 5'6" ABOVE FINISHED FLOOR.
3. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
4. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
5. CONSULT HEATER SPECIFICATION SHEET AND I & O INSTRUCTIONS. FOR FURTHER INFORMATION PLEASE VISIT WWW.SPACERAY.COM



Title: GARDNER-WEBB UNIVERSITY
INDOOR SWIMMING POOL
INSTALLATION DETAIL-1038

Drawn By: R.J. Harrington Date: 16 JUN 05