



INFRARED HEATING REQUIREMENTS

1. (4) L TS75-20 VENTED SPACE-RAY INFRARED HEATERS. INSTALL AT 45° AND AT 12 FT. ABOVE FINISHED FLOOR.
2. (2) SPACE-RAY RT SERIES THERMOSTATS MOUNTED 56" ABOVE FINISHED FLOOR.
3. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
4. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
5. CONSULT HEATER SPECIFICATION SHEET AND I & O INSTRUCTIONS. FOR FURTHER INFORMATION PLEASE VISIT WWW.SPACERAY.COM



Title: LONG BAY CAR WASH
INSTALLATION DETAIL-984

Drawn By: R.J. Harrington Date: 07 MAR 06