



INFRARED HEATING REQUIREMENTS

1. (1) CB50-N5 VENTED SPACE-RAY INFRARED HEATER. INSTALL AT 8 1/2 FT. ABOVE FINISHED FLOOR.
2. (1) SPACE-RAY SETBACK 5000 THERMOSTAT MOUNTED 5'-6" ABOVE FINISHED FLOOR.
3. HEATERS SHALL BE "PULL THROUGH" SYSTEMS (VACUUM) WITH CAST IRON BURNER AND CALORIZED EMITTER TUBES.
4. HEATER, THERMOSTAT LOCATIONS SUBJECT TO FIELD VERIFICATION & COORDINATED WITH OTHER EQUIPMENT IN THE BUILDING.
5. CONSULT HEATER SPECIFICATION SHEET AND I & O INSTRUCTIONS. FOR FURTHER INFORMATION PLEASE VISIT WWW.SPACERAY.COM
6. HEATER TO BE ROOF VENTED.
7. INSTALL PROPER SECOND STAGE REGULATORS AND VENTS IF ABOVE 1/2PSIG GAS SUPPLY.



Title: COLD BLOCKER INSTALLATION DETAIL
 TWO CAR GARAGE
 CHARLES JONES RESIDENCE - 960

Drawn By: RJ Harrington Date: 05 JUL 06